BRUHATH BANGALORE MAHANAGARA PALIKE ,DASRAHALLI ZONE
Office Of The Executive Engineer, Dasarahalli Division
SCHEDULE-B

NAME OF THE WORK: Improvements to Asphalting At Prashanth Nagar & Kalyana Nagar In Ward No.13 Mallasandra Shettyhalli Sub Division

Sl No	Description Of Work	Unit	Qty	Rate To Be Quoted	
				In Figures (Rs)	In Words (Rs)
1	2	3	4	5	6
1	Removing And Resetting Footpath Slab Page No 266 /Item No37.56/PWD SR 2016-17	Sqm	972.00	132.50	One Hundred Seventy Two Rupees And Fifty Paisa Only
2	Excavation for road drains and similar works and delisting of drain	Cft	600.00	175.96	One Hundred Seventy Five Rupees and Ninety Six paisa Only
3	Providing & laying reinforced cement precast slabs of mix CC 1:11/2:3 using 20mm & down size graded Granite metal using HYSD 10mm dia steel @ 100mm c/c both ways & Complete as per specifications.	Sqm	34.56	1680.00	One Thousand Six hundred Eighty Rupees Only
4	KSRRB 300-3. Earthwork excavation by manual means in ordinary soil involving in average horizontal throw up to 2m & an average lift up to 1.5m , excavated surface leveled & sides neatly dressed , the disposed earth to be leveled neatly after breaking of clods complete as per specification MORTH/ Chapter 3. Page No. 143/ Item No. 19.14/ PWD SR 2016-17	Cum	883.98	137.80	One Hundred Thirty Seven Rupees And Eighty Paisa Only
5	KSRB300-67 Extra For Rolling To Specifications With Power Roller When Earth is at Suitable Moisture Content with Desired Field Density not less than 95% of Maximum Dry Density(Ordinary Proctor test) Including HOM Of Machineries Complete as Per Specifications. KBS Page No.150 Item No 19.75	Cum	883.98	8.48	Eight Rupees Forty Eight Paisa Only
6	Providing, laying, spreading and compacting graded stone aggregates to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. Specification No. 406 with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work.(PWD SR 2016-17, P.No.158, Item No.20.18)	Cum	615.90	1768.08	One thousand Seven Hundred Sixty Eight Rupees And eight Paisa Only

Signature Of Contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer
Dasarahalli Division

Scanned by CamScanner

7	Providing and applying primer coat with S.S. Bitumen emulsion on prepared surface of granular base including clearing of road surface and spraying primer at the rate of 0.6 kg / sqm using mechanical means complete as per specifications, with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work.(PWDSR 2016-17, P No 161, I No 21.6)	Sqm	3212.40	29.68	Twenty Nine Rupees Sixty Eight Paisa Only
8	KSRRB 500-11. Providing and laying bituminous macadam on prepared surface with crushed coarse aggregates as per design mix formula for base / binding course including loading of aggregates with F.E. loader, hot mixing of stone aggregates and bitumen in hot mix plant, transporting the mixed material in tipper to paver and laying mixed materials with paver finisher to the required level and grade, rolling by power roller to achieve the desired density, but excluding cost of primer / tack coat including lead, lift and cost of all materials, labour, HOM of machineries complete as per specifications. Do - using 40/60 T P H capacity H.M.P. with Mechanical paver Gr-II cum (50 mm to 75 mm) with 3.4% VG-30 Bitumen Page No 162 I No 21.11, 21.11.6	Cum	147.33	5669.90	Five Thousand Six hundred Ninety Nine Rupees And Ninety Paisa Only
9	Cleaning the existing black topped surface with brooms, soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatment including cost of all materials, labour, HOM of machineries complete as per specifications Engineer-in-charge of the work (PWDSR 2016-17, P.No.161, Item No.21.2)	Sqm	3984.00	3.18	Three Rupees Eighteen Paisa Only
10	Providing and applying tack coat using 80/100 grade bitumen (VG10) on the prepared black topped surfaces at 2.5 kg per 10 sqm, heating bitumen in boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM of machineries complete as per specifications Engineer-in-charge of the work (PWDSR 2016-17, P.No.161, I No.21.7)	Sqm	6399.00	12.72	Twelve Rupees And Seventy Two Paisa Only
11	KSRRB M500-19. Providing and laying bituminous concrete with hot mix plant, using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 500.9 complete in all respects complete as per specifications.- do - using40/60 TPH capacity H.M.P. with Mechanical Paver Gr-II cum § (30 mm to 45 mm) with 5.4% VG-30 Bitumen Page No-165 Item No 21.22.6	Cum	255.96	8013.60	Eight Thousand Thirteen Rupees Only

Sig... EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer,
Dasarahalli Division,

Scanned by CamScanner